# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT34121

## APPROVED SCHEDULE - B

**EE/BTP/BBMP/E-PMT/19/2018-19, Date: 06.02.2019**

**Improvements of Roads and Drains in Kodigehalli A K Colony and Surrounding areas in ward no 08 Kodigehalli**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of V SENDHIL KUMAR ( ) | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 420.06 | Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. i) Lime /Cement Concrete. I. By Manual Means: A. Lime Concrete, cement concrete grade M-10 and below. MORTH Specification No. 202 | Cum | 390.0 | Rupees Three Hundred Ninety Only |
| 2 | 64.35 | Dismantling size stone masonry in clay mortar and stacking the size stone within a radius of 50m and removing the debris to a distance upto 200m. including cost of materials, labour, HOM complete as per specifications | Cum | 235.0 | Rupees Two Hundred Thirty Five Only |
| 3 | 21.45 | Excavation in marshy soil upto 3m depth for foundations of structures as per drawing and technical specifications including removing the excavated stuff to a lead of 15m., including dewatering , shoring strutting wherever necessary watering and ramming including cost of all materials, labour, HOM complete as per specifications MORTH Chapter 12 | Cum | 878.0 | Rupees Eight Hundred Seventy Eight Only |
| 4 | 36 | Diversion of water course by providing Coffer dams or bunds or islands as may be necessary for piers and abutments foundations, bailing out or pumping water during excavation and until completion etc., complete. - - beyond 1.50 mtrs depth upto & including 3m depth | Cum | 255.0 | Rupees Two Hundred Fifty Five Only |
| 5 | 80.44 | Providing and Filling in foundation with granite / trap broken metal 100mm. and down size & with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. | Cum | 2111.0 | Rupees Two Thousand One Hundred Eleven Only |
| 6 | 26.81 | Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement 180kgs,with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @o.57 cum machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost all materials, labour, HOM of machinery, curing complete as per specifications | Cum | 4434.0 | Rupees Four Thousand Four Hundred Thirty Four Only |
| 7 | 178.75 | Providing and removing centering, shuttering, strutting,propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per Specification. | Sqm | 382.0 | Rupees Three Hundred Eighty Two Only |
| 8 | 257.4 | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. | Sqm | 311.0 | Rupees Three Hundred Eleven Only |
| 9 | 139.42 | Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - Ready mixed Cement concrete for Beams, Staircase and Roof with M-25 | Cum | 4720.0 | Rupees Four Thousand Seven Hundred Twenty Only |
| 10 | 13.94 | Providing T.M.Tsteel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members whereever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. | Tonne | 61860.0 | Rupees Sixty One Thousand Eight Hundred Sixty Only |

Signature of the contractor



Executive Engineer

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of V SENDHIL KUMAR ( ) In Figures | In Words |
|---|---|---|---|---|---|
| 11 | 30 | Providing Weep Holes KSRRB M2200-8. Providing weep holes in Brick masonry / Plain / Reinforced concrete abutment, wing wall / return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing foce. Complete as per drawing and Technical Specifications complete as per specifications MORTH Specification No.2706 & 2200 | No | 127.0 | Rupees One Hundred Twenty Seven Only |

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

04/07